

9-249W

Job No.

K-83

PER SATURN OIL &amp; GAS CO., INC. -

Cheyenne, Wyoming

#2 McCANDLESS "A"

Moran Brothers

ELD Panoma (CG Gas)

SI Gas Well, Ga 6,579,000 Cfgpd (5 hr BD)  
from CG 2794-2899

S-T-R 35-30S-37W

SPOT App C SW

CO GRANT (Ks)

ELEV 3073 GR 8-5

(GR Log)

Winf	2540	+	538
U/FR	2612	+	466
-L/FR	2664	+	414
CG	2780	+	298
LTD	3039	+	39

to DST's, RTD 3040, Log, 5" @3039 w/200 sx.

MIST 4/2897-99 (CG), 250A, § 2 BW w/NS/2 hrs,

PF 12/2876-82, 20/2850-60, 6/2840-43, 6/2829-32, 20/2809-

19, 8/2794-96 (CG), 3000A &amp; 100 ball sealers, Ga 124,000

Cfgpd, Re-Acid, 1000A &amp; 60 ball sealers, Frac 80,000 gell

wtr x 60,000# sd, Ga 663,000 Cfgpd &amp; mist wtr, Ran 1½"

bg @2792, Ga 6,363,000 Cfgpd w/mist wtr from 2794-2899 QA, 5 hr BD Ga 6,579,000

fgpd, - CG 2794-2899 - SI Gas Well - COMPLETED on 9-21-65

Data Inc

Liberal Electric Log Logs

3073 GL

Winfield

2548 + 525

C.G.

2792 + 281 @ 6,579 MCF

TD

3039

L-S 3076 EDF  
3073 GL

MISC DATA

GEOLOGICAL No Geol on test

ELEV 3078 KB

SPUD DATE 8-10-65

FTG 1250 FSL x 1250 FWL of SW/4

3077 DF

DRLG COMP

SUPPT

FR by DATA 8-2-65

CSG 8" @646 w/400 sx, 5" @3039 w/200 sx.

C IP by 9-23-65