


90165

5-201W MAP NO. 82 SEC. 36-30S-41W
 STATE Kans COUNTY Stanton LOC. C NE SW
 OPER. The Hefner Prod. Co. (Okla. City, Okla.) FT/FR _____ LINE _____
 WELL #1 FARM Walker Unit FT/FR _____ LINE _____
 HOLE Wildcat* ELEV. 3372 GR. 3379 DF. 3382 KB _____
 CONT. Holm Drlg. GEOL. Co. Geologist
 CO. INT. 5700' Gas Test
 F.R. 4/4/63 SPUD 4/15/63 COMP. 5/21/63
 TD. 5600 FM. Mississippian/1m PBD. _____



COMP. RECORD

* 2 Miles So. of Morr Gas (Beauchamp Pool).
 8 5/8" @ 1579' w/580 sx

D&A

Data Inc.

(KB) Log

Chase	2198	+1184	Morr sd	5327-38	-1945
Cg	2539	+ 843	Morr sd	5373-98	-1991
Top	3207	+ 175	Morr sd	5452-60	-2070
Tor	3673	- 291	Miss lm	5455	-2073
Lans	3710	- 328	LTD	N.A.	
Marm	4355	- 973	RTD	5600	-2218
Morr sh	5033	-1651			

DST #1 (Perm) 2210-2310, Op 1 hr, WB/1 hr, R 60' M, ISIP 481#/30", IFP 44#, FFP 50#, FSIP 422#/30".

DST #2 (CG) 2912-60, Op 1 hr, R 150' Mdy SW + 450' SW, ISIP 481#/30", IFP 91#, FFP 284#, FSIP 481#/30".

DST #3 (Morr) 5328-35, Op 1 hr, R 100' M, ISIP 1757#/30", IFP 53#, FFP 53#, FSIP 1101#/30".

DST #4 (Morr) 5370-88, Op 1 hr, R 5' M, ISIP 686#/30", IFP 0#, FFP 0#, FSIP 74#/30".

DST #5 (Morr) 5454-74, Op 1 hr, WB & Died/12", R 84' M, ISIP 1410#/30", IFP 48#, FFP 174#, FSIP 1186#/30".

RTD 5600, Welex Log, D & A.

COMPLETED. (5/13/63)

LIBERAL ELECTRIC LOG TOPS

3382 KB

Winfield 2256 (+1126)
Topeka 3206 (+176) (tst XW in Wab)
Heebner 3652 (-270)
Toronto 3673 (-291)
Lansing 3762 (-380)
Marmaton 4354 (-972)
Morrow 5028 (-1646)
"S-3" 5327 (-1945) 3/11; tst mud
"S-3" 5374 (-1992) 6/25; tst mud
Keyes 5452 (-2070) 6/8; tst mud
Chester 5460 (-2078)
Ste. Gen 5502 (-2120)
TD 5600 D & A