

PANHANDLE EASTERN PIPE LINE CO.
Towler No. 1.

SEC. 26 T. 30 R. 37W
Gen Sec.

Total Depth. 2850'
Comm. 7-3-37 Comp. 8-6-37
Shot or Treated. 175 Qts.
Contractor.
Issued. 10-2-37

County. Grant



CASING: Rotary 2386
Cable 2850
10 3/4" 483'
7 " 2372'

Elevation.

Production. 5,328,000 G.

Figures Indicate Bottom of Formations.

no log 2386	2386
sdv lime	2396
brkn lime	2412
lime grey	2470
shale brown	2475
lime grey	2510
red rock	2535
lime grey	2570
sdv lime	2580
shale	2600
brkn lime	2605
lime grey	2645
brkn lime	2660
lime hrd	2665
red rock	2675
lime grey	2705
red rock	2720
lime grey	2765
red rock	2775
lime grey	2790
red rock	2800
lime	2825
red rock -hole caving	2835
lime	2840
sand & chert	2850
Total Depth.	

Hole making 2 BW every hr 2845-2850

Production record

Increase O.F. .600	2445-2450
Increase O.F. 1,036	2500-2505
Increase O.F. 2,000	2570-2580
Increase O.F. 2,200	2805
O.F. before shot 2,024	
O.F. after shot 5,328	