


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.

PANHANDLE EASTERN PIPE LINE CO.
Parsons No. 1.

SEC. 34 T. 30 R. 37W.
NW. SE
200' S 400' E of Center.

Total Depth. 2674
Comm. 6-24-39 Comp. 7-17-39
Shot or Treated.
Contractor.
Issued. 9-16-39

County Grant.



CASING.

103/4" 614'
7" 2410'

Elevation.

Production. 39,462,000 Gas.
after acid.

Figures Indicate Bottom of Formations

surface	20
sand	102
surface sand & gravel	320
gyp	360
sand hard and gyp	480
gyp and sticky shale	510
gyp and sticky shale	580
sticky shale	600
red bed	800
gyp shells and red bed	1015
red bed	1085
red rock	1170
red bed and shells	1270
red rock and gyp shells	1490
gyp and red bed	1610
anhydrite	1635
red rock and hard sand	1676
gyp	1772
gyp and shale	1864
gyp and red rock	1940
sand hard gyp and red rock	2005
gyp and red rock	2115
broken anhydrite and red bed	2188
anhydrite & broken shale	2260
gyp	2297
anhydrite	2352
anhydrite and lime shells	2394
shale blue	2400
lime	2407
sdv lime	2417
lime	2427 gas 1/2 million.
shale blue and lime	2431
lime	2465 Gas 5 million
shale blue and red	2475
shale red	2480
lime	2520 Gas 9 1/2 million.
shale red	2556
lime	2674
Total Depth.	

9,675,000 cu ft gas. nat.
39,462,000 cu ft gas after acid.