

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas

Company - STANOLIND OIL & GAS CO.
Farm - Pirtle Gas Unit No. 1.

SEC. 31 T. 30 R. 38 W
SW 1/4 NE
2540' SNL 2540' WEL NE 1/4

Total Depth. 2646'
Comm. 9-4-47 Comp. 10-10-47
Shot or Treated.
Contractor.
Issued. 12-20-47 Rotary 0-2430
Cable 2430-2646

County. Grant
KANSAS



CASING:
9 5/8" 556' Com.
7" 2428' Com.
5 1/2" 2399' liner 2399-2646'

Elevation. 3125 feet

Production. 8,175,000 G.
20-min. O.F.; 400#
Shut-in Pressure

sand & shells	0-535
red bed	564
red bed, sand, shells,	
lime wh hd	1210
lime	1245
red bed & shale	1660
red bed & gyp	1720
red bed	1777
red bed shale & anhyd.	2326
anhydrite, shale, lime	2430
lime	2480
shale & lime	2497
red rock, shale, lime	2544
lime & shale	2624
lime	2646
Total Depth.	

Schlumberger Ran to 2432
T. D. 2646

Acidizing:

All zones AW 2000 Gal. 15%,
Displaced, Max Press. 400#
Broke to vac. Time 20 min.
All zones REAW 13000 Gal. 15%
10500 gal flush. 6 pump trucks
Treating Press 200#. no Break.
Pumping Time, Acid 10 min. Wtr
10 min.

Herrington-Krider 2427-2467
Winfield 2482-2506
Towanda 2544-2572
Ft. Riley 2590-2622