

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 E. Murdock, Wichita, Kansas

Company - HUGOTON PROD. CO.
 Farm - Dunn

No. 1

SEC. 34 T. 30 R. 38W
 SW SW NE
 2538' W of EL & 2734'
 N. of SL
 County. Grant

Total Depth. 2669

Comm. 6-20-49


Comp. 7-11-49

Shot or Treated.

Contractor. Walter Kuhn Drng.

Issued. 9-24-49

KANSAS



3149 m

Elevation. 3148 Ind

CASING:

10 3/4" OD 600' cem. w/325 sx. Circ.
 7" OD 2449' cem. w/300 sx. Circ.

Production. 7,026,000 gas

Figures Indicate Bottom of Formations.

clay, sand & gravel	555
red bed	610
red bed & shale	848
red bed & sand	1195
anhyd.	1295
red bed & sand	1417
sand	1435
sand & shells	1465
red bed & shale	1705
anhyd. & red bed	1815
anhyd. & shale	1895
anhyd., gyp & shale	2120
anhyd. & shale	2110
anhyd. & gyp	2180
anhyd., gyp & shale	2255
lime	2455
Cable tool	
lime	2515
shale	2525
lime	2575
shale	2592
shale red	2600
lime	2689
Total Depth	

Tops:	
Hollenberg	2395
Herrington	2443
Krider	2456
Winfield	2519
Ft. Riley	2598
Lower Ft. Riley	2655

Gas Log.
 First gas
 Increase

Blow down to

" " "

" " "

Increase

Blow down to

" " "

" " "

2625	4,867 MCF
4,867 MCF	at 2660
4,867 MCF	at 2681
4,658 MCF	at 2687

Well tested 7,026 MCF on July 14, 1949 on
 72 hour shut-in test before acid. Rock
 pressure before acid: 425.0# S.G.

2460 Show

2537 to 2540 Amount not shown

2540 to 2550 6,038 MCF 2550

4,867 MCF at 2570

4,635 MCF at 2600

4,635 MCF at 2617