


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HUGOTON PRODUCTION COMPANY
 Farm- Sughrue No. 1

SEC. 35 T. 30 R. 38W
 SE SE SE NW
 2400' E. of NL & 2400' S. of NL

Total Depth. 2700
 Comm. 4-18-52 Comp. 5-3-52
 Shot or Treated.
 Contractor. Moran Bros., Inc.
 Issued. 9-13-52

County Grant KANSAS



CASING:
 10 3/4" 507' cem. w/325 sx circ.
 7" 2454' cem. w/800 sx circ.
 5 1/2" 257' OD slotted liner

Elevation. 3153 Gr.
 Production. 32,912,000 Gas

Figures indicate Bottom of Formations.

surface	40
sand & clay	50
sand & shale	475
red bed	520
red bed & gypsum	920
shale & gypsum	2275
shale, gypsum, & anhydrite	2342
anhydrite & shale	2410
anhydrite & lime	2465 RTD
lime	2536
Odell shale	2546
lime	2590
Gage shale	2610
lime	2700
Total Depth	

Tops:	
Hollenberg	2413
Herington	2457
Krider	2475-2536
Winfield	2547-2591
Upper Ft. Riley	2610
Lower Ft. Riley	2652

<u>Gas Log</u>	<u>M.C.F.</u>
2477	Show
2500	5,034
2536	4,997
2560	4,815
2572	4,749
2577	4,635
2590	4,749
2610	4,543
2629	4,589
2635	4,634
2656	4,887
2684	5,285
2700	5,184