


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company STANOLIND OIL & GAS CO.
Farm Baughman Gas Unit "B" No.1

SEC. 9 T. 30 R. 39W
Center of Section

Total Depth. 2535'
Comm. 8-17-46 Comp. 8-24-46
Shot or Treated.
Contractor.
Issued. 11-2-46

County. Stanton
KANSAS



Elevation. 3201

Production. 688,000 MCF

CASING:

8 5/8" 597' Cem.
5 1/2" 2496' Cem.

Figures Indicate Bottom of Formations.

clay	0-35
sand	154
sand gravel	392
sandy & limey clay	535
lime gy parus	554
red rock	1090
red rock & sand	1200
shale & red bed	1450
sand & red bed	1625
shale & red bed	1700
anhydrite & gyp	1740
lime brkn	1845
red bed & lime	2005
red bed & shale	2110
anhydrite & shale	2140
lime & shale	2205
shale & anhydrite	2290
lime & shale	2425
lime	2535
Total Depth.	

Tops:
Herrington 2320-2362
Arider 2381-2414
Winfield 2456-2479
Ft. Riley 2496-2530