


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - STANOLIND OIL & GAS CO.
Farm - Shetler Gas Unit "B" No. 1

SEC. 10 T. 30 R. 39W
SW SW NE
2490' SN1 & 2490' WE1 NE/c

Total Depth. 2535'
Comm. 3-24-48 Comp. 4-6-48
Shot or Treated. Acidized
Contractor.
Issued. 8-7-48

County. Stanton
KANSAS



CASING:
10-3/4" 585' Cem. W/350 Sx.
7" 2319' Cem. W/350 Sx.

Elevation. _____

Production. 20 min. open flow
14,476,000 Gas. SIP 420#.

Figures Indicate Bottom of Formations.

clay	120
sand & gravel	540
red bed	950
red bed & sand	1120
red rock	1150
gyp & anhydrite	1250
red rock	1750
red rock & anhydrite	2135
shale & lime RTD	2340
lime brkn	2350
lime	2370
lime brkn	2380
red rock	2390
lime	2400
shale blue	2430
shale red	2440
lime	2490
red rock	2500
lime	2535
Total Depth	

Schlumberger ran to 2340'

Acidization:

ALL zones AT 2000 gals. 15%
Displaced, Max. press. 300#
Broke to Vac. Time 12 mins.
REAT 16,000 gals. 15% 12,300
gals. flush. Max. press. 50#
Broke to vac. time on acid
11 mins., time on wtr 8 min.
Used 6 pump trucks.

Tops:

Herington-Krider	2319-2363
Vinfield	2393-2418
Towanda	2433-2472
Ft. Riley	2498-2435