

KANSAS DRILLERS LOG

API No. 15 — 187 — 20,126
County Number

Operator

Amoco Production Company

Address

P. O. Box 432 - Liberal, Kansas 67901

Well No.

2

Lease Name

Collingwood Gas Unit "A"

Footage Location

2640 feet from (X) (S) line 1250 feet from (E) (X) line

Principal Contractor

F.W.A. Drilling Company

Geologist

Spud Date

8-25-73

Total Depth

2915

P.B.T.D.

2860

Date Completed


9-15-73

Oil Purchaser

S. 32 T. 30S R. 39 WLoc. 1250' FEL X 2640' FSLCounty STANTON

640 Acres

N



Locate well correctly

Elev.: Gr. 3222DF _____ KB 3227

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	23	663	Class "H"	400	3% CACL
Production	7-7/8	5-1/2	14	2915	Special	510	18% CACL

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	1/2	2870-85, 2681-84,
			4	1/2	2694-97, 2708-11,
			4	1/2	2718-21, 2741-44,
					2751-57, 2761-64,
					2777-83, 2799-2804,
					2816-18, 2832-40

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidize w/1500 gal 15% HCL - Set CIBP AT 2860'	2870-85
Acidize w/2500 gal 15% HCL + frac w/100,000 gal water	2681-2840
+ 100,000# sand	

INITIAL PRODUCTION

Date of first production 9-15-73		Producing method (flowing, pumping, gas lift, etc.) Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas 5,500 MCF	Water bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold) Waiting on pipeline connection			Producing interval (s) 2681-2840		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

