

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

3-30-41W

15-187-00299

COMPANY Albert E. Lukken

SEC. 3 T. 30S R. 41W

FARM Harmon

NO. 1

LOC. C SW NW


TOTAL DEPTH 5604'

COUNTY Stanton

COMM. 5-6-66

COMP. 5-25-66

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 1552' w/700 sx

ELEVATION 3389' KB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 15' Surface Sand and Clay
- 530' Sand and Clay
- 736' Gyp and Red Bed
- 1100' Red Bed and Gyp
- 1274' Red Bed, Gyp and Anhydrite
- 1552' Red Bed and Clay
- 1933' Anhydrite and Red Bed
- 2219' Shale and Shells
- 2483' Shale and Lime
- 4446' Lime and Shale
- 4513' Lime, (Little Chert) and Shale
- 5005' Lime and Shale
- 5130' Lime, Sand and Shale
- 5604' Lime and Shale
- 5604' RTD

TOPS: SCOUT	
B/St. Cor	1569
Chase	2172
Fr. Riley	2348
Council Grove	2489
Wabaunsee	2948
Tarkio	3073
Elmont	3164
Howard	3250
Topeka	3317
Heebner	3599
Toronto	3630
Lansing	3710
B/Kansas City	4248
Marmaton	4270
Cherokee	4475
Morrow ; shale	5004
Morrow sdy lime	5290
Chester	5416
ST. Benevieve	5430
St. Louis	5496