

# PICKRELL DRILLING COMPANY, INC.

100 SOUTH MAIN - SUITE 505  
 WICHITA, KANSAS 67202-3738  
 (316) 262-8427

#1 Feiertag "K"  
 Approximately W/2 SW NE  
 Section 25-30S-41W  
 Stanton County, Kansas

API#: 15-187-20,956  
 2020' From North Line of Section  
 2480' From East Line of Section  
 ELEV: 3367' KB. 3358' GL

- 3-21-01: Murfin to start MI Rig #25.
- 3-22-01: (On 3-21) Spud @ 4:30 PM. (On 3-22) Drlg. 12 1/4" hole @ 645'.
- 3-23-01: Drlg. 12 1/4" hole to 1608'. Ran 39 jts. of New 8 5/8" 24# set @ 1605', cmt w/550sx of 65-35 poz, 6% gel, 3% CC w/1/4#FC/sx, followed by 150sx of Class A, 3%CC. PD @ 12:50 PM on 3-23-01. Cmt circ.
- 3-26-01: (On 3-24) Drlg. ahead @ 1895'. (On 3-25) Drlg. ahead @ 3051'. (On 3-26) Drlg. ahead @ 3834'.
- 3-27-01: Drlg. ahead @ 4440'.
- 3-28-01: Drlg. ahead @ 4900'.
- 3-29-01: Circ. @ 5348'. No show in K-1 Sd. Prep to take DST #1 5358-5394' (K-2 Sand), Pkr failure.
- 3-30-01: Prep to drill ahead after DST #2 5312-5394', (K-2 Sand), 30"-45"-30"-45", Wk blow. Rec: 10' M. IFP 23-40#, ISIP 59#, FFP 34-40#, FSIP 53#. Latest update @ 1:30 PM - will be starting out of hole in next 30 min. w/DST #3 5399-5421', (K-3 Sand).
- 4-02-01: (On 3-30) DST #3 5399-5420', 30"-60"-30"-120", GTS 6 min, oil to surface in 20". Reversed out 42 B.O. into stock tank. IFP 939-1110#, ISIP 1240#, FFP 1240-1261#, FSIP 1281#. (On 3-31) Drlg. ahead @ 5420'. (On 4-1) RTD 5480'. LTD 5479'. Ran 128 jts. of New 4 1/2" 10.5# Csg. set @ 5477', cmt w/200 sx ASC, 10% salt w/5#KC/sx. PD @ 4:55 PM on 4-1-01. 10sx in MH, 15sx in RH. WOCT.
- 4-11-01: Area received additional heavy rains last night. Location very muddy. Weather permitting, hope to MICT next Monday.
- 4-16-01: Plan to MICT today (4/16).
- 4-17-01: On 4/16 MICT. Prep to Log and Perforate.

## KEY WELL

#3 Johns "B"  
 SW NW NE, Sec. 25-30S-41W  
 Stanton County, Kansas

### SAMPLE TOPS

Heebner	3658 (- 291)
Lansing	3750 (- 383)
Marmaton	4327 (- 960)
Morrow Shale	4982 (-1615)
Upr Mrw Sand	5112 (-1745)
Lwr Mrw Sand	5266 (-1899)
Keyes Shale	5322 (-1955)
K-1 Sand	5345 (-1978)
K-2 Sand	5355 (-1988)
K-3 Sand	5398 (-2031)
Mississippian	5415 (-2048)
RTD	5480'

- 3  
 - 4  
 +4  
 +7  
 +10  
 +16  
 +19  
 +19  
 +25  
 +24  
 +37

### ELECTRIC LOG TOPS

Heebner	3641 (- 274)
Lansing	3751 (- 384)
Marmaton	4315 (- 948)
Morrow Shale	4987 (-1620)
Upr Morrow Sand	5112 (-1745)
Lower Morrow Marker	5272 (-1905)
Keyes Shale	5326 (-1959)
K-1 Sand	5351 (-1984)
K-2 Sand	5367 (-2000)
K-3 Sand	5401 (-2034)
Mississippian	5414 (-2049)
LTD	5479'