

29-30-41W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- WM. GRUENERWALD
 Farm- Tucker No. 1

SEC. 29 T. 30 R. 41W
 C SE/4

Total Depth. 5400'

Comm. 8-11-57

Comp. 11-31-57


Shot or Treated.

Contractor. Holm Drlg.

Issued. 12-3-60

County Stanton

KANSAS



CASING:

8 5/8" 1586'

5" 5400'

Elevation. 3431' RB

Production. 1,000,000 CFG

Figures Indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE.

TOPS: ELECTRIC

Topeka	3174
Heebner Shale	3608
Toronto Lime	3636
Douglas	3668
Lansing-Kansas City	3736
Marmaton	4252
Morrow Shale	4913
Tucker Sand	5151
Morrow Sandy Limestone	5230
Keyes Sand ?	5344
Mississippian Limestone	5375

DST #1 5145-5252', op 1 hr., shut in 20 mins., shut in 20 mins. for initial bottom hole pressure. Strong blow, gas to surf. in 3 mins. Gauged 1200 MCF after 10 mins., and 1200 MCF after 1 hr., with spring gauge. Rec. 5' of gas cut mud, no show of oil or water. IBHP 1680#, IFP 150#, FFP 170#, BHP 1630#.

DST #2 5335-60', op 54 mins., shut in 20 mins., Shut in 20 mins., for initial bottom hold pressure. Very weak blow for 25 mins., and died. Rec. 35' of mud, no show of oil, gas, or water. IBEP not recorded, IFP 0#, FFP 0#, BHP 200#.