

SIDE TWO

Operator Name Mustang Companies, Inc. Lease Name Tucker Well # 1-34
 Sec. 34 Twp. 30 Rge. 41 ☐ East ☒ West County Stanton

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken ☒ Yes ☐ No
 Samples Sent to Geological Survey ☒ Yes ☐ No
 Cores Taken ☐ Yes ☒ No

Formation Description
☐ Log ☐ Sample

Name	Top	Bottom
Heebner	3,628	3,632
Lansing	3,590	4,164
Morrow Shale	4,926	5,460
Morrow Sand	5,273	5,310
Keyes Sand	5,390	5,446

See attached for DST

	Oil	Gas	Water	Gas-Oil Ratio	Gravit
Estimated Production Per 24 Hours	none bbls	500 MCF	bbls	CFPB	

METHOD OF COMPLETION

Production Interval

Disposition of gas: ☐ Vented ☐ Open Hole ☒ Perforation
☒ Sold ☐ Other (Specify)
☐ Used on Lease

5,434 to 5,440.

☐ Dually Completed

5,422 to 5,430.

CASING RECORD

☒ New ☐ Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
surface	12 1/4"	8 5/8"	24	1,550	lite common	560	2% cc
						150	3% cc
production	7 7/8"	5 1/2"	14-15#	5,549	thixset	155	10% salt 1/4# 1sx floeal

PERFORATION RECORD

Acid, Fracture, Shot, Cement Squeeze Record

Shots Per Foot	Specify Footage of Each Interval Perforated	(Amount and Kind of Material Used)	Depth
2 SPF	5,434 to 5,440	500 gal. 7 1/2% MCA	5434-5440
	5,434 to 5,440	1500 gal. MOD 202	5434-54
2 SPF	5,422 to 5,430	800 gal. 7 1/2% MCA	5422-5430

TUBING RECORD Size 2 7/8 Set At 5,375 Packer at 5,375 Liner Run ☐ Yes ☒ No

Date of First Production March 16, 1987 Producing Method ☒ Flowing ☐ Pumping ☐ Gas Lift ☐ Other (explain).....