

2-28

To: 1 020198
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 8685
Operator: William Gruenerwald & Associates
Name & Address Box 909
Colorado Springs, CO 80901

API NUMBER 15- N/A
SE NE, SEC. 30, T 30 S, R 41 W/E
3300 feet from S section line
660 feet from E section line
Lease Name Reed Well # 1
County Stanton 172.71
Well Total Depth 5314 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1547

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 8 a.m. Day: 26 Month: 12 Year: 19 88

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service RECEIVED (phone) 316-624-7455

were: 5 1/2" at 5453' Perfs at 5148-64, 5312-14' STATE CORPORATION COMMISSION

1st plug set CIBP at 5040' with 2 sx cement on top, JAN 6 1989

2nd plug run 50 sx cement at 1600-1400'

3rd plug run 40 sx cement at 700-540', CONSERVATION DIVISION
Wichita, Kansas

4th plug run 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 2:30 p.m. Day: 28 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5040' with 2 sx cement on top,

2nd plug pumped 50 sx cement at 1600-1400',

3rd plug pumped 40 sx cement at 700-540',

4th plug pumped 10 sx cement at 40-0'. Heavy mud between all plugs.

Remarks: Used common cement by Sargent's. Recovered 1600' of 5 1/2" casing.
Additional description is necessary, use BACK of this form.)

INVOICED

(did / XXXXXX) observe this plugging.

DATE 1-11-89

INV. NO. 23614

12-28

Signed Glenn R. Barlow
(TECHNICIAN)