


3-134W  
 MAP NO. \_\_\_\_\_ SEC. 6 TWP. 30S RGE. 33W  
 STATE Kans COUNTY Haskell LOC. C SE SE  
 OPERATOR Helmrick & Payne. FT. FROM \_\_\_\_\_ LINE  
 WELL NO. 2 FARM NAME Hoffman "B" FT. FROM \_\_\_\_\_ LINE  
 CORNER Lemon NW ELEV. 2981 GR. 2989 DF. 2991 KB  
 FR. 2/7/62 SPUD. 2/5/62 COMP. 3/13/62  
 CONT. Co Tools /GEOL.



NAME PRODUCING INTERVAL		COMPLETION RECORD		TREATMENT RECORD	
		FROM - TO	PERF. W/HOLES		
a					
b					
c					
d					

a I. P. OIL/DIST. \_\_\_\_\_ WTR. \_\_\_\_\_ GAS \_\_\_\_\_ M.C.F.P.D. \_\_\_\_\_ CHK. \_\_\_\_\_ HRS. \_\_\_\_\_  
 b " " " " " "  
 c " " " " " "  
 d \_\_\_\_\_

D & A

D & A ( )

SIP#	FI TP #	FI CP#	SIBHP
			4651

GOR.		GR.		PBTD		TD	
SIZE	DEPTH	CASING - W/SAX.	CEMENT RECORD	SIZE	DEPTH	W/SAX.	
8 5/8"	775	400					
4 1/2"	4510	250					

OPERATOR Helmrick & Payne WELL NO. 2 Hoffman "B" ELEV. 2991 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB Tops & Datums					
			Hb	4082	-1091
RTD (Lans)	4651	-1660	Tor	4109	-1118
			Lans	4174	-1183

*Lo Tor + No Lsg A*

DST #1 (Tor Lans) 4148-4206, Op 60", R 210' HO & GCM, IBHP 1134#/30", IFP 80#, FFP 161#, FBHP 943#/30".  
 DST #2 (Lans) 4616-20<sup>D</sup>, Op 60", R 400' Mdy SW, IBHP 1275#/30", IFP 55#, FFP 196#, FBHP 1275#/30".  
 RTD 4651. KB Log. 4 1/2" @ 4510 w/250 sx. DV Tool 2916 w/250 sx. MICT, 24/4444-50<sup>G</sup> (Lans) 500 A, Rec 1d Swb 1-1/3 BFPH (6% Oil)/NT; 4500 A, (15%), Swb 1-2/3 BFPH (6% Oil), PB 4278, 6/4230-34<sup>A</sup> (Lans) Swb 2 1/2 BSWPH no sho, PB 4220, 72/4177-95 (Lans) 3000 A, Swb 1d, Swb 6 BFPH, 8% Oil/NT. D & A.

COMPLETED

LIBERAL ELECTRIC LOG TOPS

2991 KB

Winfield 2718 (+273)

Heebner 4086 (-1095)

Toronto 4107 (-1116)

Lansing 4174 (-1183) Tst 210' HO&GCM "A"; Swb XW "A<sub>1</sub>" &  
\$ 6 BF1PH, 8% oil - "C"

"D" Zone 4622 (-1631) Tst XW

TD 4651 D & A