

27-30-7W

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **LEBEN DRG., INC.**

SEC. 27 T. 30 R. 7W
 LOC. C SE SW

FARM **Thomas** NO. 1

COUNTY **Kingman**

TOTAL DEPTH **5010**
 COMM. **3-7-66** COMP. **3-23-66**
 SHOT OR TREATED
 CONTRACTOR **Leben Drlg.**
 ISSUED **3-6-66**



CASING

20 10
 15 8 5/8" @ 217' w/200 sx.
 12 6
 13 5 1/2" @ 5010' w/150 sx.

ELEVATION **1625' KB**

PRODUCTION **DRY**

FIGURES INDICATE BOTTOM OF FORMATIONS

0	115	Sand	TOPS: SCOUT
115	217	Redbed, Shale	
217	1000	Redbed	Heebner 3310
1000	1575	Shale, Lime	*Douglas 3415
1575	2010	Lime, Shale	Lansing 3560
2010	2425	Shale, Shells	Kansas City 3615
2425	2612	Shale	*Base K.C. 4070
2612	3797	Lime, Shale	Mississippi 4263
3797	4041	Lime	Kinderhook 4690
4041	4238	Lime, Shale	Simpson 4764
4238	4313	Shale, Lime	*Arbuckle 4890
4313	4365	Lime, Shale	
4365	4375	Dolomite Chert	* SAMPLE TOP
4375	4546	Mississippi	
4546	4625	Lime	
4625	4635	Mississippi	
4635	4656	Kinderhook	
4656	4740	Shale, Lime	
4740	4756	Lime, Shale	
4756	4770	Shale, Lime	
4770	4773	Simpson	
4773	4809	Sand	
4809	4827	Simpson	
4827	4860	Sand, Shale	
4860	4899	Sand, Lime	
4899	4937	Arbuckle	
4937	5010	Lime	
	<u>5010</u>	<u>RTD - Set 5 1/2" Casing</u>	

 Set 8 5/8" new 24# casing @ 217' with 200 sacks Common, 2% cc

I, Doug Boyd, do hereby certify that the above and foregoing is a true and correct copy of the log of the Thomas #1 well located Approximately SE SW of Section 27, Township 30 South, Range 7 West, Kingman County, Kansas, as reflected by the records of Leben Drilling, Inc.

Doug Boyd

Doug Boyd