

12-332W Map No. K-84

OPER PAN AMERICAN PETR. CORP - Liberal,
Ks.

WELL #3 M.H. WILLIAMS


OR Murfin Drlg.

FIELD Victory (KC Oil, Des M & Mrw Gas) - "C"

I.P. P 81 BOPD, Gr 35.4°, Lans "F" 4408-10

P 54 BOPD & 5% wtr, Gr 38.9°, Lans "A"

4139-41 - Dual Completion



S-T-R 7-30S-33W

125' W/C SE SE

CO HASKELL (Ks)

ELEV 2966 KB

(KB Log)

Hb	3993	-1027
Tor	4072	-1106
Lan-A	4139	-1173
Lan-B	4193	-1227
Lan-F	4406	-1440
KC-A	4598	-1632
KC-B	4660	-1694
Des M	4750	-1784
Mrw	5221	-2255
Mrw sd	5332	-2366
B/sd	5359	-2393
Chest	5378	-2412
Ste G	5398	-2432
St L	5484	-2518
Salem	5646	-2680
LTD	5702	-2736

No DST's, No Cores, RTD 5700, Rng Logs

5" @4955 w/250 sx., go?

CO, Pf 12/4787-87 (Des M), 250A (15%), § 1d, § 46

2/3 BO - NW/13 hrs, § 1 2/3 BOPH w/SSG/3 hrs (Gr 35 deg),

1000A (15%), § 1d, § 2 BOPH/4 hrs w/SSG, PB 4545, Pf 8/

4408-10 (Lan "F"), 250A (15%), § 1d, § 102 BO & 9 BW/

16 hrs w/SSG, PB 4350, Pf 8/4166-68 (Lan "A"), 250A (15%)

§ 8 3/4 BO & 44 1/2 BW/8 hrs,

Sq 4166-68 w/175 sx., Pf 8/4139-41 (Las "A"), 250A (15%),

§ 1d, § 60 BO & 27 BW/15 hrs, CO 4915. PB 4750, Ran

2 1/6" tbg w/pkr @4380

State Pot: P 81 BOPD (Gr 35.4 deg) from Lans "F" 4408-

10 (10-14-65) State Pot: P 54 BOPD & 5% wtr, Gr 38.9

deg from Lans "A" 4139-41 (12-22-65) Dual Completion

Lans only, Des M not producing) - COMPLETED 12-22-65

Data Inc

MISCEL DATA

GEOL _____

FTG _____

SUPPT _____

CSG 8" @766 w/650 sx. 5" @4955 w/250 sx.

LS

ELEV E 2963 DF

2957 GR

SPUD DATE 8-15-65

DRLG COMP _____

FR by DATA 8-13-65

COMP by " 12-29-65

*Revised
Abak. City Super*

LIBERAL ELECTRIC LOG TOPS

2966 KB

Winfield 2686 (+180)

Heebner 4050 ~~(-1084)~~ 3993(-1027)

Toronto 4072 (-1106)

Lansing 4138 (-1172) ϕ 54 BOPD

"C" Zone 4406 (-1440) ϕ 81 BOPD

"D" Zone 4598 (-1632)

D.M. Marmaton 4750 (-1784)

Pay Zone 4778 (-1882)

Morrow 5220 (-2254)

Sand 5338 (-2372) \rightarrow *chestu 5378(-2412)*

Ste. Gen 5398 (-2432)

St. Louis 5562 ~~(-2546)~~ 5484(-2518)

Por 5600 (-2634)

Salem 5646 (-2680)

TD 5702