

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


10 - 30 - 8W

Company- GULF OIL CORP.  
Farm- Tom Higgins No. 1

SEC. 10 T. 30 R. 8W  
NE SW SW

Total Depth. 4275' PB 4240'  
Comm. 2-29-56 Comp. 3-15-56  
Shot or Treated.  
Contractor.  
Issued. 5-12-56

County Kingman  
KANSAS



Elevation. 1520' DF

Production. 5,250,000 CFG

CASING:

8 5/8" 213' cem w/200 sx  
4 1/2" 4275' cem w/125 sx

Figures indicate Bottom of Formations.

red bed 213  
red bed, shale & shells 1155  
shale & shells 1325  
shale w/strks anhy 1415  
shale & lime 1630  
lime & shale 2060  
shale & shells 2505  
shale & lime 3210  
soft lime 3290  
sandy lime 3412  
lime & shale 3560  
shale & lime 3605  
lime & shale 3685  
lime 3845  
lime & shale 3930  
lime 4020  
lime & shale 4080  
lime 4275  
Total Depth  
Plugged back to 4240'

Tops:	Sample	Sch.
Heebner	3187	3186
Lansing	3411	3416
Mississippi Chert	4111	4110
Mississippi Lime	4199	4199

Perf. 4182-4190' w/r jets per foot. Fractured  
w/5544 gallons oil, 1/10# adomite per gallon  
and 7500# sand.