

10 - 30 - 8w


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- BEARDMORE & SUTTON  
Farm- Morris No. 1

SEC. 10 T. 30 R. 8W  
SW SW NE

Total Depth. 4240  
Comm. 10-15-54 Comp. 10-29-54  
Shot or Treated.  
Contractor. Beardmore Drlg. Co.  
Issued. 1-22-55

County Kingman  
KANSAS



Elevation. 1507 DF

Production. dry

CASING:

8 5/8" 150' ocm. w/100 sx  
5 1/2" 4240' ocm. w/75 sx

Figures indicate Bottom of Formations.

|                |      |
|----------------|------|
| cellar         | 5    |
| sand           | 30   |
| shale & shells | 1285 |
| lime & shale   | 3670 |
| lime           | 3955 |
| lime & shale   | 4125 |
| lime           | 4190 |
| lime & chert   | 4240 |
| Total depth    |      |

Tops:  
Lansing 3388  
Kansas City 3388

DST #1 4150-70 Gas to surface in 1 1/2 min.  
Gauged 2,200,000 cu. ft. in 7 min.  
Open 1 hr. max. 1,540,000 1 hour.  
Shut in 20 min. Recovered 90'  
OCM in the last 15', had some wtr  
in it. IF 335 FF 255 BHP 1306;  
Hydro 2322. Drilling ahead.

DST #2 4170-4190 Gas to surface in 40  
min. Open 1 hr. Shut in 20  
min. Rec. 130' GM - SOC IF 40  
FF 53 BHP 655. Not maximum.  
Hydrostatic 2322. Finished taking  
test 4190-4210; open 1 hr. shut  
in 20 min. Rec. 70' mud.

DST #3 419-4210 Open 1 hr. Weak blow-  
shut in 20 min. Rec. 70' mud.  
IF 40 FF 53 BHP 241 Not max.  
Hydrostatic 2322. TD 4240.  
Ran electric log; set 5 1/2" w/75  
sx @ 4240.