

6-30-8W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **MAGNOLIA PETROLEUM CO.**
Farm- **Hageman Unit No. 1**

SEC. **6** T. **30** R. **8W**
SE NW NE

Total Depth. **4343'**
Comm. **3-6-58** Comp. **3-21-58**
Shot or Treated.
Contractor. **Garvey Drilling Co.**
Issued. **6-7-58**

County **Kingman**
KANSAS



CASING:
8 5/8" 324' cem w/250 sx.
5 1/2" 4339' cem w/200 sx.

Elevation. **1587' RB**

Production. **174 BOPD, NW AND**
268,000 CFG

Figures Indicate Bottom of Formations.

surface sand & red bed	40
shale, shells & red bed	325
red bed & shells	470
red bed & shale	1315
shale & shells	1350
salt 1	1440
shale & lime	1735
lime 1	1920
shale & lime	2275
shale	2915
lime & shale	3588
lime	3968
lime & shale	4166
chert & shale	4215
chert	4300
lime	4340 RTD
lime	4343
Total Depth	

TOPS:	SAMPLE	SCHLUMBERGER
Heebner sh	3259	3264
Lansing-Kansas City ls	3483	3487
Mississippi cx	4184	4187
Mississippi ls	4297	4301

DST #1 4182-4215, open 1 hr g/2", ga 3310 MCF/30"
& held, rec. 40' GCM, FP 365-405#, IBHP 1600#
in 20", FBHP 1600#/40".

DST #2 4250-4300, open 30", g/2" flo cln gassy oil/9",
FP 908-1240# (Max. 1310#), rec. 300' oil (36° API),
IBHP 1658#/20", FBHP 1645#/40".

Perf. 4280-90 w/40 sh. Acidized perms. w/250 GMC, MP 1350#, min.
850#, rate 1 BPM.

Ran Schlumberger

Producing Formation Mississippian "chat"