


3-216W *84*
 MAP NO. _____ SEC. 8 TWP. 30S RGE. 33W
 STATE Kans COUNTY Haskell LOC. C SW NE
 OPERATOR Pan American Pet Corp FT. FROM _____ LINE _____
 WELL NO. 1 FARM NAME Correll GU FT. FROM _____ LINE _____
Lemon NW ELEV. 2966 GR. 2971 DF. 2974 K.B. _____
 FR. 1/31/62 SPUD 2/4/62 COMP. 3/20/62

CONT. Prime Drlg Tools /GEOL. _____

NAME PRODUCING INTERVAL	COMPLETION RECORD FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a			
b			
c			
d			



D & A _____ D & A () _____

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____
 GOR. _____ GR. _____ PBD _____ TD 4875

SIZE	DEPTH	CASING - CEMENT RECORD W/SAX.	SIZE	DEPTH	W/SAX.
<u>8 5/8"</u>	<u>768</u>	<u>550</u>			

OPERATOR Pan American Pet Corp WELL NO. 1 Correll GU ELEV. 2974KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB tops & datums			Chase	2633	+ 341
RTD (Des M)	4875	-1901	Cg	2926	+ 48
			Penn	3466	- 492
RTD 4875. Welex log 4853.			Tor	4112	-1138
5 1/2" @ 4875 w/350 sx. 8/			Mo	4154	-1180
4817-19 (Lans) \$ no sho nat			Lans	4182	-1208
500A, \$ 1d, \$ 4 1/2 BFWPH,			Des M	4782	-1808
12 hrs, PB 4800, 16/4788-			LTD (Des M)	4853	-1879
90 (Des M) No tst Nat, 500A					
(15%) \$ 2 1/2 BFWPH/4 hrs, W/ sli sho gas, \$ 27 1/2 BFW/11 hrs,					
(Cumm) Sq 4817-19 & 4788-90 w/100 sx. CO & Reperf,					
16/4788-90 (Des M) 500A, \$ 1d, \$ 13 BO + 38 BW/17 hrs,					
\$ 3 BO + 16 BW/7 hrs, 3000A (15%) \$ 1d, \$ 10 BO +					
25 BW/6 hrs, \$ 7 BO + 27 BW/24 hrs, D & A 3/12/62.					

COMPLETED

