

DRILL STEM TESTS

McCoy Petroleum Corporation

#3-3 Whitmer "S"

SE NW SW

Section 3-30S-9W

Spivey-Grabs Field

Kingman County, Kansas

API# 15-095-21,753

Spud Date: 6-18-99

DST #1 2858-2879' (Howard)

Open 30", S.I. 30", Open 30", S.I. 30"

Strong blow, OBB/ ½" on 1st open,

Strong blow, OBB/ 9 ½" on 2nd open.

Recovered 540' of slightly muddy water.

ISIP 972# FSIP 941#

FP 48-163# 178-242#

RELEASED

DEC 17 2001

FROM CONFIDENTIAL

DST #2 4255-4268' (Mississippian)

Open 30", S.I. 60", Open 60", S.I. 90"

Gas to the surface in 8 minutes,

Gauge 18,800 CFGPD in 10" on 1st open period,

" 23,600 CFGPD in 20"

" 61,400 CFGPD in 30"

Gauge 104,000 CFGPD in 10" on 2nd open period,

" 116,000 CFGPD in 20"

" 132,000 CFGPD in 30"

" 147,000 CFGPD in 40"

" 147,000 CFGPD in 50"

" 150,000 CFGPD in 60"

Recovered 25' of slightly gas cut mud,

120' of slightly water cut mud (90% mud, 10% water).

ISIP 880# FSIP 876#

FP 21-54# 40-90#