


Company - STELBAR OIL CORP.  
Farm - Ludwig No. 3

29-31-1W  
SEC. 29 T. 31 R. 1 W  
C SL NE NE

Total Depth. 3710'  
Comm. 7-17-44 Comp. 8-5-44  
Shot or Treated.  
Contractor. E.B. Shawver  
Issued. 10-14-44

County. Sumner  
KANSAS



CASING:  
8  $\frac{1}{4}$ " 342' Cem.  
5  $\frac{1}{2}$ " 3675' Cem.

Elevation. \_\_\_\_\_

Production. Est. 50 B.

Figures Indicate Bottom of Formations.

surface	45
shale & shells	1080
lime	1129
shale & shells	1975
lime	2160
shale	2180
lime	2220
shale	2635
sand	2830
shale	3060
K.C.lime	3350
shale	3671
chat & lime	3710
Total Depth	

IP 15 bbls. oil per day nat.  
in chat-Miss lime.

Acidized 8-6-44 w/5000 treatment

Production after acid, 50 bbls.  
oil per day, est.