

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
 Union National Bank Bldg, Wichita, Kansas,

PLOTTED  
 G.E. Jamison  
 29-31-1W


E.B. SHAWVER ET AL.  
 W.H. Neel, No. 2.

SEC. 29 T. 31 R. 1W.  
 NE SE SE

Total Depth. 3706  
 Comm. 4-11-35 Comp. 6-14-35  
 Shot or Treated. 1000 gal acid  
 Contractor. E. B. Shawver.  
 Issued. 8-17-35

County. Sumner.

AUG 17 1935



CASING.

20"	48'11"	8 1/4"	2756 UR2840
15 1/2"	365'	65/8"	2285' UR 3663
12 1/2"	1278'		
10"	2156'		

Elevation.

Production. Pot. 221.70 B.

Figures Indicate Bottom of Formations.

soil	10	slate	1015	shale light	1805
shale	170	red rock	1017	lime ha rd	1820
red rock	175	lime	1040	shale dark	1840
shale	225	shale	1050	shale	1860
salt and shale	260	lime	1070	lime	1950
shale blue	270	shale	1080	shale	2000
lime	275	lime	1100	lime hard	2027
salt	310	slate	1105	shale light	2032
shale soft	335	lime	1130	lime	2160
slate blue	350	red rock	1135	shale blue	2163
shale blue	370	lime shells	1160	lime	2190
lime	380	lime	1175	slate	2195
shale blue	400	slate	1180	shale	2205
lime	415	lime	1185	lime	2210
shale blue & shells	440	shale blk	1190	shale	2240
lime	450	lime	1200	lime	2250
slate & lime shells	485	shale	1205	shale	2305
shale and shells	490	lime	1215	lime	2375
lime	500	shale	1225	slate blk	2380
lime shells	515	lime	1240	lime	2385
lime	530	sdv lime	1260	slate blk	2390
slate	535	lime shells	1277	lime	2405
lime	550	lime	1315	shale dark	2430
shale	560	shale	1330	lime	2460
lime	565	lime	1340	shale	2470
shale	575	shale	1350	lime	2490
lime	590	red rock	1353	shale blue	2550
shale	600	shale	1380	lime	2565
lime	615	slate white	1390	shale	2675
red rock	619	lime	1400	lime	2680
lime	625	shale	1465	shale blue	2690
lime shells	665	lime	1470	sdv lime	2880
shale blue	680	shale	1490	slate	2873
lime	690	shale white	1500	shale	3018
shale	695	shale blk	1520	shale blue	3046
lime	700	shale white	1530	K.C. lime	3178
shale	705	shale blue	1570	shale	3180
lime	725	lime	1575	lime	3266
shale	740	shale light	1590	lime blk	3277
sdv shale	765	lime	1600	lime	3282
sdv lime	785	shale	1610	slate blk	3294
slate blue	800	lime	1615	lime	3299
lime	850	shale blue	1620	slate blue	3305
slate	875	lime	1640	shale blue	3315
lime	885	shale	1660	lime	3328
shale	892	lime	1670	shale	3350
lime	899	shale	1675	lime	3380
shale	905	lime	1705	shale blue	3385
red rock	910	shale	1710	lime	3400
lime	935	lime	1715	shale	3405
sdv lime	945	shale	1730	lime	3410
lime	955	lime	1750	shale	3418
shale	960	shale	1760	lime	3428
red rock	965	lime	1765	shale	3450
lime	975	shale	1775	sdv shale	3460
shale	980	lime	1795		
lime	1005	shale	1800		

OVER

lime	3470
shale	3475
lime	3507
shale and shells	3537
lime	3555
shale blk	3565
shale hole caving	3587
shale	3602
red rock	3611
shale	3645
V.C. shale	3660
chat	3674
brown lime & grey chat	3683
brown lime soft pay	3696
dark lime hard	3706
Total Depth	

WATER RECORD.

1 EW 750-760  
 2 EW 810-25  
 3 EW 935-45  
 2 BWH 1240-55  
 HFW 2705-15

REMARKS.

Top of lime 3660  
 Small show gas Rainbow of oil.  
 Chat 3666-74. More gas and oil.  
 Brown lime and grey chat 3674-83  
 brown lime soft pay filled 2000'  
 of oil 3683-96 Dark lime hard  
 3696-3706. TD. no likely pay last 10'  
 Well did not flow natural.

Acidized June 21, and 23 two shots of 1000 gal each  
 Well averaged 221.70 bbls on two day Pot, after  
 acidizing.