

29-31-1W


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - COOPERATIVE REFINING ASSN.
Farm - Riddell No. 2

SEC. 29 T. 31 R. 1W
SE NE SW

Total Depth. 3690 PB 3672
Comm. 11-5-48 Comp. 1-9-49
Shot or Treated. 1000 gals. Reacidized w/3000 gals.
Contractor. H. J. Uhl
Issued. 2-26-49

County. Sumner
KANSAS



Elevation. 1257 ft.

Production. 48 BOPD

CASING:

8 5/8" 155' cem w/100 sx.
5 1/2" 3653' cem w/150 sx.

Figures Indicate Bottom of Formations.

surface	160
shale, shells	283
shale, salt	314
salt, shells	342
shale, shells	425
salt	525
shale, shells	565
salt strks	690
shale, shells	855
lime	965
red rock	985
shale, lime	1050
lime	1115
lime, shale	2485
lime	2580
lime, shale	2640
lime	2670
shale, shells	2780
lime	2795
shale, lime	2829
lime	2885
shale	2900
lime strks	2960
lime, shale	3030
lime	3206
shale	3225
lime	3298
shale	3345
lime	3355
lime, shale	3440
lime	3505
lime, shale	3625
shale	3642
chat RTD	3659
Drill Pipe Corr: =	3669

dolomitic chert and
dolomite 3690
total depth
PB 3672

Tops:

Lansing, K.C. 3034
Mississippi 3648

Acidized thru casing w/1000 gals.
reacidized w/3000 gals.