

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


32-31-1W

Company - BRIDGEPORT OIL COMPANY, INC.
Farm - Frankum No. 2

SEC. 32 T. 31 R. 1W
NE SE NW

Total Depth. 3681'
Comm. 4-9-48 Comp. 6-3-48
Shot or Treated. Acidized
Contractor.
Issued. 7-31-48

County. Sumner
KANSAS



Elevation. 1246 ft.

Production. Pot. 68 BO & 10 BW

CASING:

8-5/8" 135' Cem. w/100 sx
5-1/2" 3655' Cem. w/125 sx

Figures Indicate Bottom of Formations.

shale, shells & sand 0-135
shale 195
shale, salt & shells 495
shale & shells 845
lime 1140
shale & shells 2005
lime 2400
lime & shale 2693
sand 2723
lime & shale 2755
lime, shale & sand 2855
shale & shells 3090
shale & lime 3164
lime 3320
sand 3367
lime 3495
lime & shale 3658
3658= 3656 D.F.
lime 3681
Total Depth

Tops: (Derrick Floor)

Stalnaker 2684
Lansing-Kansas City 3028
Mississippi 3653

Show of gas 3668, first free oil at 3671. Increase in oil 3671-3676, filled 750' in 7 hours. Swabbed 30 1/2 BO in 16 hrs. Acidized w/3000 gallons, maximum pressure 800 lbs., broke to 500 lbs., dropped to 50# in 2 minutes. Pumped 68 Bo, estimated 10% water.