

32-31-1W


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - STELBAR OIL CORP.  
Farm - Markloy No. 1

SEC. 32 T. 31 R. 1 W  
NEc SW

Total Depth. 3701'  
Comm. 3-27-47 Corp. 5-1-47  
Shot or Treated.  
Contractor. E. D. Shawver Petro. Corp.  
Issued. 6-21-47

County. Sumner  
KANSAS



## CASING:

10" 140' Cem. w/65 sx.  
5½" OD 3659' Cem. w/100 sx.

Elevation. 1241 feet

Production. Est. 10 BO.

Figures Indicate Bottom of Formations.

surface	30
sand	45
shale	2012
lime	2235
shale	2710
shale sdy	2814
shale	3036
K. C. Lime	3255
shale	3658
chat & dolomite	3701
Total Depth.	

## Tops:

K. C. Lime 3036-3255  
Chat - Mississippi 3658-3701

Acidized w/5000 gal. of 15% solution  
No. test 6-11-47

Coarse chert 3659-60'  
Coarse cherty dolomite  
a few sat. pieces 3660-70'  
Cherty dolomite, med  
por. - fair sat. 3670-78'  
dolomite cherty,  
tighter - fair sat. 3678-87'  
dolomite cherty, med  
tight - lgt. sat. 3687-94'  
dolomite cherty, med  
tight - lgt sat. 3694-3701'