

STELBAR OIL CO.
Erker No. 8.

SEC. 33 T. 31 R. 1W
~~NW NE SW~~

Total Depth, 3680
Comm. 11-17-36 Comp. 12-16-36
Shot or Treated, 1000 & 4000 Gals.
Contractor, E.B. Shawver
Issued, 1-16-37

County, Sumner

CASING:

10" 331'
6 5/8" 3624'

JAN 16 1937



Elevation.

Production Pot. 930 B.

Figures Indicate Bottom of Formations.

surface	20	shale	1910
shale	140	lime	1925
shale & shells	210	shale	1960
salt & shale	290	shy lime	2050
shale & shells	318	lime	2157
shale	331	shale	2162
shale & shells	660	lime	2245
lime	675	shale	2300
shale & shells	740	lime	2320
lime	750	shale	2365
shale & shells	810	lime	2375
lime	825	shale	2395
shale & shells	880	lime	2406
lime	895	shale	2418
shale	910	lime	2440
lime	935	shale	2650
shale	945	shy lime	2750
lime	970	shale	3006
shale	1010	K.C. lime	3140
lime	1027	shale	3145
shale	1060	lime	3183
shale & shells	1085	shale	3188
shale	1105	lime	3240
lime brkn	1118	shale	3245
lime	1140	lime	3255
shale & shells	1185	shale	3268
shale	1234	lime	3290
shale & shells	1343	shale	3310
lime	1350	lime	3340
shale	1412	shale	3360
lime	1425	lime	3374
shale	1565	shale	3430
lime	1580	lime	3452
shale	1595	shale	3610
lime	1605	V.C.	3623
shale	1622	ohat & lime	3680
lime	1645	Total Depth.	
shale	1705		
lime	1725		
shale & shells	1748	Swabbed 15-20 bbls. natural in 1 hr test	
shale	1760	Potential 930 B.	
lime	1770		
shale	1790		
lime	1814		
shale	1875		
lime	1895		