

26-31-1W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. SKELLY OIL CO.
Farm. G. A. Spitler No. 2

SEC. 26 T. 31 R. 1W
SW NW NW
990' fr NL, 330' fr WL, NW/4

Total Depth. 3701 PBSD 3676.5
Comm. 9-12-55 Comp. 9-23-55
Shot or Treated. Perf. 53/3659-68 & 1000 gals. acid
Contractor. Chas. Hulme Drilling Contractor
Issued. 1-21-56

County Sumner
KANSAS



8 5/8 @ CASING: 358' w/ 250 sx cmt.
5 1/2 @ 3701' w/ 150 sx cmt.

Elevation. 1273 DF

Production. 335 BOPD

Figures indicate Bottom of Formations

surface soil, sand & gravel	200
sand, shells & shale	280
shale & shells	340
anhydrite	358
lime & shale	400
lime	1205
lime & shale	1570
shale & shells	1800
lime & shale	2555
shale	2730
shale & lime	2850
shale	2975
shale & lime	3143
light gray, fine crystalline lime w/ spotted oolitic & oolitic porosity	3149
lime & shale	3645
Core #1: rec. 39'	3684
shale	3701
Total Depth	

Plugged back to 3676.5

TOPS:

Stalnaker	2651
Kansas City	2992
Base K. C.	3276
Marmaton lime	3324
Cherokee	3518
Mississippi lime	3640
Mississippi dolomite	3652

Ran Schlumberger Survey.

DST #1: packer @ 3649, 35' anchor,
open 1 hr. gas to surf. 24 min. gauged
37,686 cu' rec. 70' SOCM, 60' HOCCM,
120' muddy oil, IFP 40#, FFP 120#,
BHP 1270#/20 min.

Producing Formation: Mississippi
dolomite 3659-68.