

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


26-31-1W

Company. SKELLY OIL CO.
Farm. G. A. Spitler No. 4

SEC. 26 T. 31 R. 1W
SW NE NW
990' fr NL 990' fr EL NW/4

Total Depth. 3710 PBTB 3685.5
Comm. 10-14-55 Comp. 10-25-55
Shot or Treated. Perf. 59/3651-61: 1000 gal acid 3651-61
Contractor. Chas Hulme Drilling Contractor
issued. 2-4-56

County Sumner
KANSAS



8 5/8 @ CASING; 358' w/ 250 sx cmt.
5 1/2 @ 3710' w/ 150 sx cmt.

Elevation. 1272 DF

Production. 173 BOPD

Figures indicate Bottom of Formations

surface soil, shale & shells	130
shale & shells	325
anhydrite	358
lime	600
shale & lime	1070
lime	1275
lime & shale	2840
lime	2950
lime & shale	3035
lime	3215
lime & shale	3395
lime	3490
shale & lime	3590
shale	3642
Cored: rec. 37' 6"	3680
lime	3710
Total Depth	

Plugged back to 3685.5

TOPS:

Anhydrite	325
Stalnaker	2645
Kansas City	2995
Base K. C.	3226
Marmaton	3327
Cherokee lime	3517
Mississippi lime	3641
Mississippi dolomite	3650

Ran Schlumberger Survey

DST #1: packer @ 3650, 30' anchor,
open 1 hr, gas to surf. 43 min. too
small to gauge, rec. 180' HO&GCM, 120'
MCO, 5' SW, IFP 15# FFP 100#, BHP
1025#

Producing Formation: Mississippi
dolomite 3651-61