

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

26-31-1W


Company- SKELLY OIL CO.
Farm- G. A. Spitler No. 5

SEC. 26 T. 31 R. 1W
NE SW NW
990' fr SL, 990' fr WL NW/4

Total Depth. 3716' PB 3675'
Comm. 10-28-55 Comp. 11-8-55
Shot or Treated.
Contractor. Chas. Hulme Drlg. Co.
Issued. 3-3-56

County Sumner

KANSAS



Elevation. 1276' DE

Production. 85 BO

CASING:

8 5/8" 358' cem w/250 sx
5 1/2" 3716' cem w/150 sx

Figure 1. locate Bottom of Formations

surface soil, shale & shells	205	
sand	270	
shale and shells	325	
anhydrite and lime	358	
shale and shells	400	
lime	540	
shale and shells	805	
lime	1005	
lime and shale	2490	
shale	2730	
shale and lime	2835	
shale	3002	
lime	3230	
lime and shale	3655	
Cored	3655-3695	Rec. 40'
lime and shale	3716	
Total Depth		
Plug back to 3675'		

Tops:

Kansas City Lime	3000
Base Kansas City Lime	3257
Marmaton Lime	3336
Cherokee Lime	3530
Mississippi Lime	3654
Mississippi Dolomite	3662

Ran Schlumberger Survey

Acid Treatments:

#1 11-12-55 between 3662-3671' used
1000 gallons of acid and 108 BO.

#2 11-19-55 between 3662-3672' used
1000 gallons of acid and 103 BO.

Producing formation Mississippi Dolomite Top 3662' Bottom 3672'