

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

18-31-1W
Anson South Unit B 3-1

Company- A. F. BRANN
Farm- Wagoner

No. 1

SEC. 18 T. 31 R. 1W
SE SE SW

Total Depth. 3750'

Comm. 4-9-59

Comp. 4-20-59


Shot or Treated.

Contractor. Shawver-Armour

Issued. 8-8-59

County Sumner

KANSAS



Elevation. 1264' DF

Production. 90 BOPD

CASING:

8 5/8" 426' cem w/280 sx.

5 1/2" 3745'

Figures indicate Bottom of Formations.

DRILLERS LOG NOT AVAILABLE:

Core #1 3733-3738' Recovered 5 feet.
2 feet dark blue flaky shale, 3' light
greenish gray shale w/numerous chert
nodules.

Core #2 3738-3744', Recovered 4 feet.
4 feet light greenish gray shale w/
numerous large chert nodules, and few
thin streaks of gray to white lime.
A very slight odor of gas in bottom of
core on fresh break. No oil staining
was noted.

TOPS: SAMPLE

Stalnaker	2784
Base Stalnaker	2847
Lansing	3075
Mississippian	3735
Mississippi Dolomite	3744

Rotary Total Depth 3750

DST #1 3744-3750', Halliburton Tester -
Tool op 1 hr., very strong blow thruout
test. Gas surfaced in 45". Rec. 260'
of fluid, 20' being very heavily oil cut
mud, and 240' of gassy oil, ISI & FSI 20".
IBHP 1395#, IFP 30#, FFP 120#, FBHP 1335#.