

7-31-1W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BEARDMORE, ET AL
Farm- Zoglmann "C" No. 1

SEC. 7 T. 31 R. 1W
C W/2 SW SE

Total Depth. 3731'
Comm. 11-5-58 Comp. 11-14-58
Shot or Treated.
Contractor. Beardmore Drlg.
Issued. 2-7-59

County Sumner
KANSAS



CASING:
8 5/8" 425' cem w/300 sx.
5 1/2" 3722' cem w/75 sx.

Elevation. 1277' DF

Production. 202 BOPD

Figures Indicate Bottom of Formations.

cellar and soil	15
shale, shells & lime	275
shale and lime	425
lime	675
lime and shale	1455
shale, lime & sand	1890
shale and lime	2745
sand	2835
lime and shale	3005
shale	3058
lime	3250
lime and shale	3380
lime	3435
lime and shale	3680
shale, lime & chert	3721
shale, lime & chert	3730 RTD
shale, lime & chert	3731 CTTD
Total Depth	

TOPS:

Kansas City	3055
Mississippi Line	3717
Mississippi Dolomite	3721

DST #1 3719-3727, shut in 20 min., op 1 hr., shut in 20 min., gas in 40 min.
Rec. 45' oil & gas cut mud, 60' very heavy oil & gas cut mud, some free oil, 60' muddy gassy oil. IBHP 1310, FBHP 1300#, IF 15#, FF 60#, Temperature 109°.
Hydrostatic 2055#.

Core #1 3721-3727 Rec. 6' - Dolomite, show of oil.

Core #2 3727-3730 Rec. 3' - Dolomite, show of oil.