


8 - 31 - 1W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- PETROLEUM TRADING & TRANSPORT CO. ET AL SEC. 8 T. 31 R. 1W  
Farm- Zoglmann No. 1 NE SE SW

Total Depth. 4060  
Comm. ~~3-25-51~~ Comp. 4-30-51  
Shot or Treated.  
Contractor. Donald T. Ingling  
Issued. 6-14-52

County Sumner  
KANSAS



CASING:  
8 5/8" 327'  
5 1/2" 4058'

Elevation. 1303 DF

Production. 86 BO & 25% wtr.

Figures Indicate Bottom of Formations.

surface clay & shale	50
shale & shells	327
lime & shale	355
shale & salt	370
lime & shale	570
shale & shells	660
shale & lime	820
lime	900
shale & lime	1525
shale & shells	1635
lime & shale	1895
lime	1965
lime & shale	2025
lime	2215
shale & lime	2275
shale & shells	2365
shale & lime	2450
lime & shale	2630
shale	2740
sand hrd	2760
sand	2785
sand & shale	2806
shale & lime	2865
sand & shale	2880
shale	2945
shale & iron strks	2980
shale	3044
lime	3301
shale & lime	3665
shale	3668
lime	3685
shale & lime	3700
lime hrd	3714
lime	4020
lime & shale	4036
simpson sand	4044
sand	4060
Total Depth	

Scout Tops:	
Topeka	1998
Iatan	2738
Stalnaker	2742
Kansas City	3224
Base Kansas City	3277
Marmaton	3859
Cherokee	3484
Miss.	3668
Kinderhook	3985
Simpson Sand	4036