

8 - 31 - 1W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PHILLIPS PETRO.
Farm- Zoglmann


No. 1

SEC. 8 T. 31 R. 1W
SW NE SW

Total Depth. 4155
Comm. 9-15-51
Shot or Treated.
Contractor.
Issued. 12-1-51

Comp. 10-15-51

County Sumner
KANSAS



CASING:
8" 371' cem. w/300 sx

Elevation. 1288

Production. Dry

Figures indicate Bottom of Formations.

surface sand	40
shale & shells	295
sand	303
shale & shells	1175
shale	1445
shale & shells	1860
lime & shale	2005
shale & shells	2130
lime & shale	2675
shale & sand	2756
shale	2815
lime	2862
shale	2897
lime & shale	2936
shale	3005
lime	3282
lime & shale	3410
shale & shells	3460
lime & shale	3553
shale & shells	3605
lime & shale	3690
lime	3931
lime & shale	3958
lime	4004
lime & shale	4012
cored, lime	4032 $\frac{1}{2}$
lime	4033
cored, lime	4035 $\frac{1}{2}$
lime	4036
cored, lime	4039
lime	4155
Total Depth	

Tops:

Lansing-Kansas City	3206
Mississippi	3650
Kinderhook	3950
Simpson	4018
Arbuckle	4101

DST: 4023-35 $\frac{1}{2}$ /60/90' Sl.

gas cut mud

DST: 4103-15/47/15' mud.