

19-31-1W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BEARDMORE DRILLING COMPANY
Farm- Trekell No. 1

SEC. 19 T. 31 R. 1W
NE NE NW

Total Depth. 3727'
Comm. 3-4-59 Comp. 3-14-59
Shot or Treated.
Contractor. Beardmore Drilling Company
Issued. 5-30-59

County Sumner
KANSAS



CASING:

8 5/8" @ 402' w/275 sx.
5 1/2" @ 3718' w/75 sx.

Elevation. 1251' DF

Production. 48 BOPD

Figures Indicate Bottom of Formations.

cellar & clay	10
shale & shells	402
lime & shale	1200
shale	1675
shale, lime & sand	1990
lime & shale	2205
shale	2765
sand	2830
shale & lime	3100
lime	3495
lime & shale	3715
lime	3727 RTD
Total Depth	

TOPS: Kansas City	3080
Mississippi Dolomite	3715

Core #1. 3719-3726 Recover 7', Dolomite
with poor to fair porosity, spotted light
stain.

DST #1. 3717-3726 Packer failed - no
test.

DST #2. 3718-3727 Shut in 20 min. open
90 min., shut in 20 min. Rec. 100' slight-
ly oil cut mud. IBHP & IF - Failed,
FBHP 1410, FF 115.