


1-31-10W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. AYLWARD DRLG. CO. & SUNRAY MID-CONT. OIL SEC. 1 T. 31 R.10W
Farm. Rankin No. 1 C NE SW

Total Depth. 4641'
Comm. 9-5-61 Comp. 9-19-61
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 11-25-61

County Barber
KANSAS



Elevation. 1716' DF

CASING:
8 5/8" 206' cem w/225 sx.

Production. Dry

Figures Indicate Bottom of Formations.

sand, red bed & rock	207
red bed & shale	605
shale & shells	1290
shale	1450
shale & lime	1550
lime & shale	1640
shale & lime	1820
lime	2170
lime & shale	2355
shale & lime	2760
lime & shale	3725
shale	3763
lime	4458
lime & chert	4535
lime	4612
shale	4641 RTD
Total Depth	

TOPS: (LOG)	
Heebner	3562
Douglas	3632
Upper Douglas Sstone	3658
Lower Douglas Sstone	3706
Lansing	3774
Mississippi	4455
Kinderhook	4622

DST 4433-69', op 1 hr 5 min, Rec. 120'
Sl. GCM, 240' Sl. GCWatrMud. IBHP 1518#/45 min
FBHP 997#/60 min, FP 98#-150#.