

Company- TRANS ERA PETROLEUM, INC.
Farm- McReynolds No. 1

SEC.

30 31 32
NW NW NW

RLOW

Total Depth. 4985

Comm. 4-2-55

Shot or Treated.


Contractor.

Issued. 7-30-55

Comp. 4-28-55

County Barber

KANSAS



Elevation. 1717

Production. 20 BOPD

CASING:

8 5/8 @ 295' w/ 200 sx cmt.
5 1/2 @ 4984' w/ 200 sx cmt.

Figures indicate Bottom of Formations.

sand	50
sand & red bed	150
red rock	230
red bed	295
red bed & shale	850
shale	1200
shale & salt	1310
shale & shells	1385
lime & shale	2000
lime	2070
lime & shale	3727
lime	3783
lime & shale	3886
lime	4231
lime & shale	4494
Mississippi	4520
Mississippi chat & chert	4559
chat & shale	4580
lime & chert	4603
chert & shale	4619
lime & shale	4644
shale	4664
shale & lime	4686
shale	4741
Viola	4755
shale & lime	4791
Viola	4806
Simpson	4810
shale & sand	4827
shale	4833
sand	4882
sand & shale	4956
shale	4962
Arbuckle lime	4985
Total Depth	

SCOUT TOPS:

Elgin sand	3572
Heebner	3596
Topeka	3741
Douglas sand	3785
Kansas City	3877
Mississippi	4494
Kinderhook	4633
Viola	4741
Simpson shale	4806
Simpson sand	4834
Arbuckle	4961