

34-31-10W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- WALTERS DEILLING COMPANY
Farm- Amsden No. 1

SEC. 34 T. 31 R. 10W
 C SE SE

Total Depth. 4510'
Comm. 9-9-57 Comp. 9-24-57
Shot or Treated.
Contractor. Walters Drilling Company
Issued. 2-1-58

County Barber
 KANSAS



CASING:

8 5/8" 211' cem w/150 sx
5 1/2" 4510' cem w/100 sx

Elevation. 1571' DF

Production. 4,600,000 GFG

Figures indicate Bottom of Formations.

surface	211
shale & shells	1500
shale, shells & lime	1619
lime & shale	3700
lime	4120
lime & chert	4175
lime	4436
Chert	4510-RTD
Total Depth	

TOPS:

Heebner	3550
Douglas (Scout)	3608
Lansing-Kansas City	3736
Mississippi Chert	4422
Mississippi Limestone	4506

Ran Lane-Wells Gamma Ray & Latter Log.
Perf. 60 shots 4440-55'. 500 acid
followed by 250 water. Sand-water
frac w/19,500# sand & 704 bbls. water.
10-19-57 Perf. 100 cone shots 4440-4465.
Acid 1,000 gals.
10-25-57 Re-frac 16,450# sand, 30,000
gals. Petro-frac. Max. pressure 2900#.
Min. pressure 2350#