


90079 X

MAP NO. _____ ELEV. 3071 GR 3082 KB
 STATE Kansas COUNTY Stevens SEC. 10 Twp 31S Rge 37W
 OPERATOR Hugoton Production Co. LOC. C SE SW
 WELL NO. 2-10 FARM NAME McCreery 1976 FT. FROM W LINE
 POOL Panoma 660 FT. FROM S LINE
 FR. 9-21-60 SPUD. 9-20-60 COMP. 11-11-60

CONT./GEOL. Moran

COMPLETION RECORD		PERF. W/HOLES	TREATMENT RECORD
NAME PRODUCING INTERVAL	FROM - TO		
a <u>Council Grove</u>	<u>2847-42</u> <u>54</u>	<u>42</u>	<u>2000A, A. Frac</u>
b <u>Council Grove</u>	<u>2890-97</u>	<u>42</u>	<u>4000 GA X</u>
c <u>Council Grove</u>	<u>2913-18</u>	<u>30</u>	<u>6000# sd.</u>



d I. P. OIL/DIST. WTR. None GAS 5,950 M.C.F.P.D. _____ CHK. _____ HRS. _____
 b " " " " " " " "
 c " " " " " " " "
 d 72-20 Calc OF

SIP# 360.4 FI TP # _____ FI CP# _____ SIDHP _____
 GOR. _____ GR. _____ PSTD 2993 TD 6140

CASING - CEMENT RECORD		SIZE	DEPTH	W/SAX.
SIZE	DEPTH			
<u>13 3/8"</u>	<u>574</u>	<u>500</u>		
<u>8 5/8"</u>	<u>3061</u>	<u>500</u>		

OPERATOR Hugoton Production WELL NO. #2-10 McCreery ELEV. 3071 GR

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			DC	748	
			Blaine	1099	
			Gloryetta	1214	
			Gloryetta sd	1254	
			Cimarron anh	1674	
			Holl	2442	
			Herr	2485	
			U. Kri	2510	
			L. Kri	2540	
			Winf	2580	
			U. FR	2644	
			L. FR	2693	
			Florence Flint	2755	
			Wre	2782	
			CG	2811	
			Wab	3236	
			Shawnee	3586	
			Hb	4014	
			Toro	4044	
			Lans	4125	

E-Log Tops
Atoka 5254
Morrow 5701
No Sand (Dev)
Chester 5736

#1 DST 5338-94 (B/Atoka), op 35", WB & died, rec 30' GCM
FP 0#, ISIP 111, FSIP 44.

RTD 6140, ran elec log.

#1 WLT @ 5689, test 360 cc FW, rec all wtr, FP 175#-175#
PB 2993.

perf 42/2890-97, 30/2913-18, NS, 2000 A, g 298 MCF/7 hrs.

perf 42/2847-54, prep to frac, A/F 4 x 6, rec load, g 240 MCF
14 hrs.

72/20 OF = 5,950 MCF, SIP 360.4#. Council Grove 2847-2918
COMPLETE.

LIBERAL TOPS

3082 KB

Winfield 2580 (+502)

Council Grove 2840 (+242) IP = 6 M

Wabaunsee 3235 (-153)

Heebner 4020 (-938)

Toronto 4040 (-958)

Lansing 4135 (-1053)

Morrow 5408 (-2326) Tst FW

Chester 5735 (-2653)

tst SSG in Basal Atoka

3012
2502
502