

8-31-11W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LARIO OIL & GAS CO.
Farm- Axline "A" No. 1

SEC. 8 T. 31 R. 11W
SW NW SE

Total Depth. 3826' PB 3732'
Comm. 7-21-61 Comp. 7-31-61
Shot or Treated.
Contractor. Prime Drilg. Co.
Issued. 11-4-61

County Barber
KANSAS



CASING:
8 5/8" 325' cem w/250 sx.
5 1/2" 3783' cem w/800 gals. Latex

Elevation. 1700' DF

Production. 1,300,000 CFG

Figures indicate Bottom of Formations.

shale & red bed	95
lime & shale	330
red bed, shale & shells	770
shale & shells	1165
shale & lime	1440
Anhydrite	1455
Anhydrite, salt & shale	1733
lime & shale	2030
lime	2110
lime & shale	2240
lime	2585
lime & shale	3120
lime	3275
lime & shale	3522
lime	3587
shale & lime	3655
shale, sand & lime	3728
shale & sand	3802
lime	3826 RTD
Total Depth	
Plugged back to	3732

TOPS: CORR. W/SCHLUMBERGER
Base LeCompton Lime 3470
Heebner 3622
Douglas Sand 3728
Lansing 3826

8-3-61 Perf. 4 holes @ 3734' (sq.).
8-5-61 Dowell Abrasijet at 3730' to notch.
8-6-61 Dowell acidized w/250 gallons 15% mud acid.