

16-31-11W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LARIO OIL & GAS CO.
Farm- Watkins-Smith Unit No. 1

SEC. 16 T. 31 R. 11W
100' SW of Cen. SE NE SW

Total Depth. 3915'
Comm. 9-19-61 Comp. 10-1-61
Shot or Treated.
Contractor. Capitt Drlg.
Issued. 2-17-62

County Barber
KANSAS



CASING:
8 5/8" 341.89' cem w/275 sx.
5 1/2" 3814.90' cem w/100 sx.

Elevation. 1751' KB

Production. 14,000 MCF

Figures indicate Bottom of Formations.

| | |
|---------------------|----------|
| surface soil, sandy | 36 |
| shells & sand | 110 |
| red bed, sandy | 230 |
| red bed & shells | 570 |
| shale & shells | 1665 |
| lime & shale | 2085 |
| lime | 2437 |
| shale & lime | 3020 |
| lime | 3124 |
| lime & shale | 3915 RTD |
| Total Depth | |

TOPS:

| | |
|--------------------------|------|
| Base LeCompton | 3539 |
| Elgin Sandstone | 3586 |
| Heebner | 3716 |
| Douglas Sandstone | 3763 |
| Douglas Limestone | 3840 |
| Second Douglas Sandstone | 3852 |
| Lansing | 3896 |

10-3-61 Welex perforated 16 holes
3764-3768'.

10-4-61 Dowell acidized w/500 gals.
mud acid.