

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


17-31-11W

Company- LARIO OIL & GAS CO.
Farm- Watkins-Nelson Unit No. 1

SEC. 17 T. 31 R. 11W
NE NE SE

Total Depth. 4475' PB 3790'
Comm. 5-15-61 Comp. 5-30-61
Shot or Treated.
Contractor. Patton Drilg. Co.
Issued. 9-2-61

County Barber
KANSAS



Elevation. 1739' RB

Production. 6,150,000 CFG

CASING:

8 5/8" 318' cem w/250 sx.
5 1/2" 3826' cem w/100 sx.

Figures indicate Bottom of Formation

surface clay & sand	70
red bed & shells	920
shale & shells	1275
salt, shale & shells	1425
shale & shells	1810
Anhydrite & shale	1925
lime & shale	2140
lime	2330
lime & shale	2605
lime	2770
shale & lime	3350
sandy shale	3430
shale	3525
sandy shale	3529
sand (Elgin)	3578
sandy shale	3695
sandy shale & lime	3766
sand & shale	3859
lime	3953
chalky lime & shale	3990
lime	4286
chalky lime w/shale	4329
lime & shale	4395
lime	4475 RTD

8-20-59 Schlumberger perforated with
17 shots from 3766-3770'

Total Depth
Plugged back to 3790'

TOPS:

Base LeCompton	3514
Elgin Sandstone	3550
Heebner	3670
Douglas Sandstone	3757
Lansing	3869
Mississippian	4436
Mississippian Ls.	4468

6-1-61 Perf. w/link jet 16 holes
3759-3763' (no gas) Sq.
6-3-61 Perf. 16 holes w/swing jet from
3759-3763' sq.
6-3-61 Acidized w/250 gallons 7½% MCA.
6-7-61 Wellex perf. w/torpedo jet 8 shots
from 3759-3763.
6-8-61 Acidized w/500 gallons 7½% MCA.