


29-31-11W

LARIO OIL & GAS CO.
Whelan No. 1-B.

SEC. 29 T. 31 R. 11W.
CNE SW

Total Depth. 4358
Comm. 7-18-40 Comp. 9-11-40
Shot or Treated.
Contractor. Springrose Drlg. Co.
Issued. 10-19-40

County Barber.



CASING.

10" 128' 5 $\frac{1}{2}$ " 4312'

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

red rock	128
red rock & shale	570
shale and shells	1170
salt and gyp	1340
shale and gyp	1550
shale and lime	1600
lime and gyp	1700
shale and gyp	1750
shale lime shells	1780
shale and lime	1925
shale and shells	2035
lime	2130
shale and lime	2500
shale sticky	2520
broken lime	2550
shale and lime	2955
broken lime	3040
lime	3220
broken lime and sticky shale	3255
sticky shale	3360
shale	3440
shale sdy	3480
sticky shale	3535
sdv shale	3545
shale and lime	3585
shale	3670
sand	3705
sticky shale	3720
lime hard	3730
broken lime	3740
shale	3784
lime	3820
lime hard	3850
lime	4125
broken lime & shale	4165
lime and shale	4265
broken lime	4310
chat	4358
Total Depth.	

40 shots
95 shots