

30-31-11W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LARIO OIL & GAS COMPANY
Farm- Nuckolls No. 3

SEC. 30 T. 31 R. 11W
CN/2 N/2 SE

Total Depth. 4325
Comm. 5-3-52 Comp. 5-20-52
Shot or Treated.
Contractor.
Issued. 9-13-52

County Barber KANSAS



CASING:
8 5/8" 139' cem. w/100 sx
5 1/2" 4306' cem. w/250 sx

Elevation. 1552 DF
(555 ft)

Production. Pmp. 55 BO & 10 BW

Figures Indicate Bottom of Formations.

cellar	10
red bed	142
red rock	160
red bed, shale & shells	965
shale & shells	1250
salt, shale & shells	1515
lime & shale	2240
shale & shells	2395
lime & shale	2680
shale	2790
lime & shale	3295
shale & shells	3395
sand & shale	3412
sand	3430
lime & sandy shale	3538
sand & shale	3718
lime	3730
sandy shale	3737
lime	4005
lime & shale	4040
lime	4165
lime & shale	4306
chert	4325 RTD
Total Depth	

Tops:	
Elgin Sand	3361
Lansing	3734
Chat	4306