


30-3 P.E. HW
card made out

JAMES DAVIS
R. L. Nuckolls No. 1.

SEC. 30 T.31 R. 11W
SW 1/4 NE
330' fr WL 330' fr SL

Total Depth. 4314'
Comm. 2-24-38 Comp. 3-28-38
Shot or Treated. No
Contractor. Helmerich & Payne, Inc.
Issued. 7-2-38 Rotary

County. Barber



CASING:

JUL 2 1938

12 1/2" 103'
7" 4293'

Elevation.

Production. Pot. 1049 B.

Figures Indicate Bottom of Formations.

clay	10	lime hrd	4072
sand & gravel	30	lime	4293
shale & shells	103	ohat	4314
red rock & shells	470	Total Depth.	
red rock, shale, shells	815		
red rock & shells	1083		
red rock, shale, shells	1345	Top of ohat 4293	
shale & shells	1630	Gas at 4294 1/2	
shale, shells & strks		First oil at 4294 1/2	
pyrite	1720	Inc in oil from 4304-4309	
shale & shells	1875		
shale & sdy lime	1925	Well not acidized-no shot.	
shale & shells	2040		
lime	2050		
lime & shale	2120		
brkn lime	2250		
shale & shells	2380		
brkn lime	2470		
shale & shells	2610		
brkn lime	2770		
lime	2822		
brkn lime	2825		
lime hrd	2890		
lime	3025		
brkn lime	3085		
lime	3240		
shale	3267		
shale & lime	3445		
shale	3460		
lime	3520		
brkn lime	3540		
lime	3589		
lime sharp	3610		
lime	3615		
sdv shale & brkn lime	3705		
lime	3725		
shale & lime	3772		
lime	3790		
brkn lime	3810		
lime	3965		
cherty lime	3990		