

County Barber KANSAS



Total Depth. 4321'
Comm. 4-4-55 Comp. 4-21-55
Shot or Treated.
Contractor. D & M Drilg. Co.
Issued. 5-14-55

CASING:

8 5/8" 212' cem w/200 sx

Meas. R.B.

Elevation. 1521' KB

Production. Dry

Figures indicate Bottom of Formations.

sand	25
shale and shells	110
red bed and shells	212
plug and cement 200-212	
shale, shells, sand strks	1030
shale and lime strks	1565
shale and lime	1680
shale w/lime streaks	1881
lime	1950
shale and lime	2120
lime w/shale streaks	2270
lime and shale	2540
sandy shale & lime strks	2780
shale and lime	2910
shale	3015
lime w/shale streaks	3105
lime	3175
lime and shale	3283
shale	3360
sand	3375
sand-shale	3450
lime, shale, sand strks	3517
lime, shale and sand	3660
lime w/shale	3762
lime	4135
lime w/shale strks	4181
lime w/shale	4219
lime and shale	4270
Mississippi	4282
Chat	4292
Chert	4321
Total Depth	

Tops:

Elgin Sand	3360
Douglas Sand	3539
Ireland Sand	3677
Kansas City	3702
Mississippi	4271

DRILL STEM TESTS:

#1 3360-3375 Tool open 1 hr., gas to surface in 30 mins. Quantity not large enough to gauge. Rec. 250' muddy salt water. 20 min. SIP showed IFP 45#, FFP 95# BHP 960#.

#2 3526-3568 Tool open 1 hr., fair to weak blow. Rec. 10' mud. 20 min. SIP showed 128# BHP with no flow pressure.

#5 4272-4282 Tool open 1 hr., good blow. Rec. 75' slightly oil spotted mud. 20 min. SIP showed IFP 15#, FFP 20# and 542# BHP.

#6 4283-4292 Tool open 2 hrs., weak blow throughout. Rec. 10' slightly oil spotted mud. 30 min. SIP showed 65# BHP no flow pressure.

#7 4293-4321 Tool open 2 hrs., fair blow. Rec. 15' slightly oil spotted mud. 30 min. SIP showed IFP 15#, FFP 30# and 63# BHP.

#3 3648-3660 Tool open 1 hr., weak to fair blow. Rec. 340' muddy salt wtr., no gas. 20 min SIP showed IFP 40#, FFP 88#, BHP 1316#.

#4 3865-3885 tool open 1 hr., fair blow. Rec. 450' muddy salt water. 20 min SIP showed BHP 1555#.