

31-31-11W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas

Company OLSON DRILG. CO. & GLOBE O & R CO.
Farm Regnier No. 1

SEC. 31 T. 31 R. 11 W
CNE SW

Total Depth. 3335'
Comm 8-7-46 Comp. 8-24-46
Shot or Treated.
Contractor.
Issued. 10-12-46

County Barber
KANSAS



Elevation 1502 ft

Production. 5,800,000 Gas.

CASING:

9 5/8" 159' Cem.
5 5/8" 3316' Cem.

Figures Indicate Bottom of Formations.

sand & gravel	0-65
shale red & shells	183
sand, shale & shells	410
sand & shells	675
shale & shells	1140
sand, shale & shells	1358
salt	1485
shale & shells	1574
shale & lime	2078
lime	2130
lime & shale	2330
shale & shells	2440
shale	2575
shale & shells	2772
shale & lime	2930
shale	3000
lime	3035
shale & lime	3144
shale	3227
shale & lime	3315
sand Elgin	3335
Total Depth.	

ENT 3318-35' open 10' gas 5' min.
& 30' drlg. fluid.
Flow press. 735#
BHP 1320#