

Plotted JB

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


31-31-11W

OLSON OIL CO.
Swartz "B" No. 1.

SEC.31 T.31 R.11W
CNW NE

Total Depth. 4294'
Comm. 5-14-41 Comp. 6-1-41
Shot or Treated.
Contractor.
Issued. 7-19-41

County. Barber



CASING:
8 5/8" 135' Com.
5 1/2" 4261' Com.

Elevation.

Production. Pot.832 B.

Figures Indicate Bottom of Formations.

sand & clay	75
anhydrite & red shale	136
shale red & shells	1033
shale & shells	1160
salt, shale, shells	1495
shale	1562
shale & lime	1920
lime brkn	1950
shale & lime	2004
lime	2190
shale & lime	2240
lime sdy	2314
shale & shells	2588
shale & lime	2786
lime	2816
shale & lime	2843
shale & shells	2864
lime	2943
shale & lime	3272
lime	3275
lime sdy	3400
shale	3406
lime & shale	3514
sand & shale	3672
lime	3689
shale & lime	3690
lime	4065
shale	4081
lime	4119
lime & shale	4256
chat - RUST	4261
chat	4294
Total Depth.	

4262-4284 (well flowing
by heads.)